

CONSTRUCTION SCHEDULE

Your pool will take approximately 15 working days to complete. The following is a list of what you can expect day to day as we build your pool.

Day 1: Excavation: normal excavation with no unexpected problems (i.e. ledge; ground water; or excessive material to be removed) should be completed in one day.

Day 2: The pool package will be delivered.

Day 3: Installation crew will arrive and begin construction of the steel walls of the pool.

Day 4: Installation crew will pour the footing around the base of the steel frame and prepare the inside of the pool for the concrete base.

Day 5: Installation crew will pour the concrete base of the pool and install the plumbing of the pool.

Day 6: Installation crew will install the coping on the pool; clean the bottom concrete; install the foam padding on the walls of the pool and install the liner. At this time we will begin to fill the pool from the house unless you have contracted to have the water brought in by truck.

Day 7: Crew will remove the blowers from behind the liner when we have approximately 6" of water in the shallow end, and will install the trim plates on the parts.

Days 8 & 9: Grading around the pool will begin. Depending on how much grading is involved, it will take approximately 1-2 days to finish the grade.

Day 10: Filter system to be installed.

Day 11: Accessories to be installed (i.e. ladder, safety rope, etc.)

Day 12: Trenching for electrical service.

Days 13-15: Electrical work from house panel to pool equipment.

* the exact time of the day when crew will arrive at house during construction days cannot be predicted