

# SITE DEVELOPMENT PLANS FOR UNION SOLAR PROJECT

FRANKLIN, MASSACHUSETTS 02038


DATE: JUNE 20, 2023




 $\frac{\text{VICINITY MAP}}{1" = 1,000'}$ 



LOCUS MAP 1" = 1,000'






# **OWNER:**

JOHN C. COLELLA JR. O UPPER UNION STREET FRANKLIN MA, 02038

# **APPLICANT:**

VS UNION SOLAR SMART, LLC 24942 DANA POINT HARBOR DANA POINT, CA 92629

# **ENGINEER:**



P.O. Box 1051, Sandwich, MA 02563
PHONE NUMBER: (508) 888-9282





Sheet of 1 9


JOB NUMBER


3328.00


OVERALL LOCATION PLAN
SCALE: 1" = 100'






















(NOT TO SCALE)



1. IF FILL MATERIAL IS REQUIRED, IT SHALL CONSIST OF COMMON FILL MATERIAL FREE OF ORGANICS, FROZEN SOIL AND ROCKS GREATER THAN 6" IN DIAMETER. 2. THE BASIN SIDESLOPES AND BOTTOM SHALL BE STABILIZED USING GRASS SEED MIXTURES CAPABLE OF RESISTING THE ANTICIPATED SHEARING FORCES ASSOCIATED WITH RUN-OFF VELOCITIES. THE SEED MIXTURES SHALL BE ABLE TO WITHSTAND PERIODIC INUNDATION UNDER WATER AND BE DROUGHT TOLERANT DURING SUMMER


3. ANY SLOPE STEEPER THAN 3:1 SHALL BE EQUIPPED WITH SLOPE STABILIZATION FABRIC OR EROSION CONTROL MATTING.

## DETENTION BASIN SECTION NOT TO SCALE




SUPPORT NET

SILTATION FENCE



REFER TO MANUFACTURER'S

SPECIFICATIONS FOR ADDITIONAL INSTALLATION INFORMATION.




CHAIN LINK FENCE DETAIL (GALVANIZED)


(NOT TO SCALE)

TOP VIEW


SECTION-B


SECTION-A





(M 1.03 TYPE B)~





# (MIN.) — EXISTING PAVEMENT PLAN VIEW (MIN.) FABRIC - Mountable Berm 2 - 3" CRUSHED STONE CROSS SECTION

ENTRANCE. - IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM! WITH 5:- 1 SLOPES WILL BE PERMITTED. 7. MAINTENANCE-THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY, ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY SHALL BE 8. WHEN WHEEL WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN 9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

STABILIZED CONSTRUCTION ENTRANCE DETAIL

TOP COURSE

 $(TYPE I-1)_{-}$ 

—COMPACTED SUB-GRADE

CAPE COD BERM DETAIL

# 13. REFER TO CONSTRUCTION DETAILS FOR ADDITIONAL EROSION CONTROL 14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SITING, RELOCATION AND AUGMENTATION OF EROSION CONTROL DEVICES AS THE PROJECT PROGRESSES AND THE SITE DRAINAGE CONDITIONS 15. THE CONTRACTOR SHALL MINIMIZE THE AREA OF DISTURBED SOIL. 4. WIDTH-NOT LESS THAN 12 FEET WHERE MORE THAN ONE (1) ACCESS POINT TO THE SITE, WHERE ONE (1) ACCESS POINT A 5. GEOTEXTILE—SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE. 6. SURFACE WATER-SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCE SHALL BE PIPED BENEATH THE

BINDER COURSE

(TYPE I−1) <del>----</del>

# 1. STONE SIZE - USE 1-4 INCH STONE, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT. 3. THICKNESS-NOT LESS THAN 6 INCHES.

#### 1 1/2" BIT CONG -BINDER COURSE 1/2" BIT CONC. TOP COURSE-(TYPE I-1) (TYPE I-1) 6" GRAVEL SUBBASE (M1.03 TYPE-B COMPACTED SUBGRADE PAVEMENT CROSS SECTION NOT TO SCALE

**EROSION CONTROL NOTES:** 

UPON COMPLETION OF CONSTRUCTION.

CONSTRUCTION.

EACH RAINFALL

EXPENSE TO THE OWNER.

PROPERTY, ETC.

DISTURBED AREAS.

INSTALL EROSION CONTROL BARRIERS AND MAINTAIN THROUGHOUT

ALL DISTURBED AREAS SHALL BE LOAMED AND SEEDED IMMEDIATELY

ALL MATERIALS AND STOCKPILES SHALL BE STORED ON LEVEL AREAS

OUTSIDE OF ANY FLOOD ZONES, WETLANDS OR BUFFER ZONE AREAS.

SIDE SLOPES NO GREATER THAN 30% AND SHALL BE SEEDED OR

STABILIZED IF LEFT UNDISTURBED FOR TWO WEEKS OR MORE.

STABILIZATION FABRIC OR EROSION CONTROL MATTING.

ALL STOCKPILES SHALL BE SURROUNDED BY HAYBALES, SHALL HAVE

SEDIMENTATION CONTROL DEVICES AND EROSION CONTROL BARRIERS

SHALL BE INSPECTED WEEKLY AND MAINTAINED AS NECESSARY THROUGHOUT ALL PHASES OF CONSTRUCTION AND PROMPTLY AFTER

ADDITIONAL EROSION CONTROL MEASURES SHALL BE INSTITUTED AS

CONDITIONS WARRANT OR AS DIRECTED BY THE ENGINEER AND/OR

THE CONTRACTOR MUST REPAIR OR RE-SEED ANY AREAS THAT DO

NOT DEVELOP WITHIN A PERIOD OF ONE YEAR AT NO ADDITIONAL

3. MATERIAL STOCKPILES SHALL NOT BE LOCATED WITHIN THE PATH OF

PERMANENT) OR THOSE AREAS SUBJECT TO STORM WATER FLOW.

9. SEDIMENT CONTROL DEVICES AND EROSION CONTROL BARRIERS MAY BE

REMAIN DISTURBED BUT INACTIVE FOR AT LEAST THIRTY DAYS, SHALL

MASSACHUSETTS EROSION AND SEDIMENT CONTROL GUIDELINES. IN

SUCH THAT RUNOFF IS DIRECTED AWAY FROM ABUTTING STRUCTURES,

ALL CASES, STABILIZATION MEASURES SHALL BE IMPLEMENTED AS

SOON AS POSSIBLE IN ACCORDANCE WITH THE MASSACHUSETTS

11. EARTHWORK ACTIVITY ON THE SITE SHALL BE DONE IN A MANNER

SILTATION FENCING FOR INSTALLATION AT THE DIRECTION OF THE

EFFORTS SHALL BE MADE TO LIMIT THE TIME OF EXPOSURE OF

ENGINEERS OR THE TOWN TO MITIGATE ANY EMERGENCY CONTROL.

12. THE CONTRACTOR SHALL KEEP ON SITE AT ALL TIMES EXTRA

EXISTING OR PROPOSED WATERCOURSES (BOTH TEMPORARY OR

10. ALL DISTURBED OR EXPOSED AREAS SUBJECT TO EROSION, WHICH

RECEIVE TEMPORARY SEEDING IN ACCORDANCE WITH THE

EROSION AND SEDIMENT CONTROL GUIDELINES.

REMOVED ONLY AFTER THE SITE HAS BEEN STABILIZED.

### **CONSTRUCTION NOTES:**

- 1. THE PROPERTY LINES AND EXISTING CONDITIONS SHOWN HEREON, ARE COMPILED FROM THE RECORD PLAN (PARCEL A-PLAN NUMBER 624 OF 1995 IN PLAN BOOK 433) AND DEED (NOOK 31678 PAGE 107) AND ARE BASED UPON THE NORTH AMERICAN DATUM OF 1983 (NAVD83) AND BASED UPON A FIELD SURVEY BY ATLANTIC DESIGN ENGINEERS, INC.
- THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS SHOWN AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES THAT MAY BE FOUND IN THE
- 3. CONTRACTOR SHALL VERIFY ALL CRITICAL ELEVATIONS AND INVERTS PRIOR TO
- 4. WHERE AN EXISTING PUBLIC UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, THE LOCATION, ELEVATION AND SIZE OF THE UTILITY SHALL
- BE ACCURATELY DETERMINED AND THE INFORMATION FURNISHED TO THE UTILITY COMPANY AND OWNER FOR RESOLUTION OF THE CONFLICT. 5. SUBSURFACE AND ENVIRONMENTAL CONDITIONS WERE NOT EXAMINED OR CONSIDERED AS PART OF THIS SURVEY. NO STATEMENT IS MADE
- CONCERNING THE EXISTENCE OF UNDERGROUND OR OVERHEAD CONTAINERS OR FACILITIES THAT MAY AFFECT THE USE OR DEVELOPMENT OF THIS SITE. 6. IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY DIGSAFE, THE TOWN OF
- FRANKLIN DEPARTMENT OF PUBLIC WORKS, AND ALL UTILITY COMPANIES A MINIMUM OF 72 HOURS PRIOR TO CONSTRUCTION ACTIVITIES FOR LOCATION OF ALL UNDERGROUND UTILITIES AND UTILITY COMPANY APPROVALS.
- ALL BUILDINGS, SURFACE, AND SUBSURFACE IMPROVEMENTS ON AREAS ADJACENT TO THE SITE ARE NOT NECESSARILY SHOWN HEREON.
- 8. THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVES. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL UTILITIES AND RIM AND INVERTS BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES THAT MIGHT OCCUR BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.
- THE CONTRACTOR SHALL MAKE ALL ARRANGEMENTS FOR THE ALTERATION AND ADJUSTMENTS OF ELECTRIC, TELEPHONE AND ANY OTHER PRIVATE UTILITIES WITH THE UTILITY COMPANY, IF NECESSARY. IF ANY INTERRUPTIONS IN SERVICE ARE NECESSARY TO ABUTTING PROPERTY OWNERS, A MINIMUM OF 48 HOURS NOTICE SHALL BE GIVEN.
- 10. THE CONTRACTOR SHALL PROVIDE TRAFFIC CONTROL MEASURES IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES AND MASSACHUSETTS HIGHWAY DEPARTMENT REQUIREMENTS FOR ALL WORK WITHIN PUBLIC STREETS
- 11. AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONTRACTOR'S OPERATION SHALL BE RESTORED BY THE CONTRACTOR TO THEIR ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.
- 12. THE CONTRACTOR IS RESPONSIBLE TO ENSURE THAT ALL REQUIRED INSPECTIONS AND/OR CERTIFICATIONS REQUIRED BY CODES AND/OR UTILITY COMPANIES ARE COMPLETED PRIOR TO INSTALLATION, BACKFILLING. ANNOUNCED BUILDING POSSESSION, AND THE FINAL CONNECTION OF
- 13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL SURVEY CONTROL POINTS AND BENCHMARKS NECESSARY FOR THE PROPOSED WORK.
- 14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ADEQUATE RECORDS OF THE LOCATION AND ELEVATION OF ALL WORK INSTALLED.
- 15. THE CONTRACTOR SHALL INSTITUTE AND MAINTAIN ALL SAFETY MEASURES NECESSARY TO PROTECT THE PUBLIC DURING CONSTRUCTION, INCLUDING, BUT NOT LIMITED TO BARRICADES, SIGNS, FENCES, FLAGGERS, LIGHTING, POLICE DETAIL, AND ANY OTHER MEANS AS DIRECTED BY THE TOWN. NO TRENCHES TO REMAIN OPEN OVERNIGHT
- 16. THE CONTRACTOR SHALL KEEP THE PREMISES FREE FROM THE ACCUMULATION OF WASTE MATERIAL AND OTHER DEBRIS RESULTING FROM THE WORK. AT THE END OF CONSTRUCTION THE CONTRACTOR SHALL REMOVE ALL CONSTRUCTION DEBRIS AND SURPLUS MATERIALS FROM THE SITE. A THOROUGH INSPECTION OF THE WORK PERIMETER IS TO BE MADE AND ALL DISCARDED MATERIALS, BLOWN OR WATER CARRIED DEBRIS, SHALL BE COLLECTED AND REMOVED FROM THE SITE.
- 17. ALL WORK SHALL BE DONE IN STRICT COMPLIANCE WITH ALL APPROVED PERMITS AND WITH ALL APPLICABLE NATIONAL, STATE, AND LOCAL CODES, STANDARDS, ORDINANCES, RULES AND REGULATIONS.
- 18. CONTRACTOR TO DESIGNATE A SPECIFIC AREA FOR COMBUSTIBLE MATERIALS, APPROVED BY THE FIRE DEPARTMENT, SO THAT COMBUSTIBLES ARE NOT SPREAD THROUGHOUT THE CONSTRUCTION SITE.

# CONSTRUCTION PERIOD STORMWATER OPERATION AND MAINTENANCE:


REPLACED COMPLETELY.

- CONSTRUCTION ENTRANCE/TRACKING PAD THE CONSTRUCTION ENTRANCE TRACKING PADS SHOULD BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOW OF SEDIMENT ONTO THE PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOPDRESSING WITH ADDITIONAL STONE. THE ENTRANCE PAD SHOULD BE INSPECTED WEEKLY AT A MINIMUM, AFTER MAJOR STORM EVENTS (>0.25" PER THE CGP) AND DURING PERIODS OF HEAVY USE. WHEN MUD AND SOIL PARTICLES CLOG THE VOIDS IN THE STONE, THE PAD SHOULD BE TOP DRESSED WITH NEW STONE OR
- EROSION CONTROL BARRIERS (HAY BALES, SILT FENCE, ETC.) SHOULD BE NSPECTED IMMEDIATELY AFTER EACH RUN-OFF PRODUCING RAINFALL EVENT (>0.25 INCHES PER 2022 CGP) AND AT LEAST DAILY DURING PROLONGED SEDIMENT DEPOSITS MUST BE REMOVED WHEN THE LEVEL OF DEPOSITION REACHES APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER. SEDIMENT SHOULD BE DISPOSED OF IN A SUITABLE AREA AND PROTECTED FROM EROSION BY EITHER STRUCTURAL OR VEGETATIVE MEANS.
- GRASSED SWALES WITH CHECK-DAMS: DURING CONSTRUCTION GRASSED LINED SWALES SHALL BE INSPECTED IMMEDIATELY AFTER MAJOR STORM EVENTS (>0.25 INCHES PER 2022 CGP) AND AT LEAST DAILY DURING PROLONGED RAINFALL. REPAIR ERODED SPOTS IMMEDIATELY AFTER INSPECTION. ADDITIONAL INSPECTIONS SHOULD BE SCHEDULED DURING THE FIRST FEW MONTHS TO ENSURE THAT THE VEGETATION IN THE CHANNELS IS ESTABLISHED ADEQUATELY. ACCUMULATED SEDIMENT SHALL BE REMOVED BEFORE IT EXCEEDS 0.5' IN DEPTH. SWALES SHALL BE MOWED AS NEEDED. CLIPPINGS TO BE REMOVED FROM SWALES AND AREAS IMMEDIATELY UP-GRADIENT AND PROPERLY DISPOSED OF.
- DEEP SUMP HOODED CATCH BASINS: INSPECT MONTHLY (MINIMUM), OR AFTER MAJOR STORM EVENTS (>0.25" PER THE CGP) DURING CONSTRUCTION FOR CLOGGED GRATES OR PIPES AND EXCESSIVE ACCUMULATION OF SEDIMENT, SAND, OR TRASH. CLEAN SUMPS WHEN SEDIMENT REACHES 24". ALL CATCH BASINS SHALL BE PROVIDED WITH PRE-MANUFACTURED "SILT-BAG" CATCH BASIN INLET SEDIMENT COLLECTION SYSTEMS UNTIL BASE COURSE IS IN PLACE.
- CATCH BASIN INLET PROTECTION ("SILT-SACKS"): ALL CATCH BASINS SHALL BE PROVIDED WITH INLET PROTECTION CONSISTING OF PRE-MANUFACTURED "SILT-SACKS" CATCH BASIN INLET SEDIMENT COLLECTION SYSTEMS UNTIL PAVEMENT BASE COURSE IS IN PLACE AND THE CONTRIBUTING DRAINAGE AREA TO THE INLET IS STABILIZED. INSPECT THE INLET PROTECTION DEVICE WEEKLY AT A MINIMUM, AND AFTER MAJOR STORM EVENTS (>0.25" PER THE CGP) THROUGHOUT CONSTRUCTION. REPAIRS ARE TO BE MADE AS REQUIRED AND SEDIMENT MUST BE REMOVED WHEN THE LEVEL OF DECOMPOSITION REACHES THE REMOVAL DEPTH PER MANUFACTURER SPECIFICATIONS.
- STONE INFILTRATION TRENCH: INSPECT AFTER EVERY MAJOR STORM EVENT (0.25" PER CGP) DURING CONSTRUCTION. ONCE SITE IS STABILIZED AND RE-VEGETATED, CUT AWAY/REMOVE TEMPORARY COVER FOLD AND INSPECT TO ENSURE PROPER STABILIZATION AND FUNCTION. REMOVE ANY SEDIMENT THAT ACCUMULATED DURING CONSTRUCTION.
- SUB-SURFACE INFILTRATION SYSTEM: INSPECT AFTER EVERY MAJOR STORM EVENT (>0.25 INCHES PER 2022 CGP) DURING CONSTRUCTION TO ENSURE THE SYSTÈM IS DRAINING PROPERLY. CHECK FOR ACCUMULATION OF SEDIMENT AND PONDING WATER. IF PONDING WATER IS VISIBLE INSIDE THE SYSTEM FOR SEVERAL DAYS AFTER A STORM EVENT. NOTIFY THE ENGINEER FOR POSSIBLE REMEDIAL MEASURES. REMOVE SEDIMENT AS NECESSARY DURING CONSTRUCTION, WHILE THE SYSTEM IS DRY.
- INSPECT AFTER EVERY MAJOR STORM EVENT (>0.25" PER 2022 GCP) DURING CONSTRUCTION TO ENSURE PROPER STABILIZATION AND FUNCTION. EXAMINE HE OUTLET STRUCTURE OR OUTLET PIPES FOR EVIDENCE OF CLOGGING OR EXCESSIVE OUTLET VELOCITIES. CHECK FOR ACCUMULATION OF SEDIMENT AND PONDING OF WATER. IF PONDING WATER ABOVE THE OUTLET PIPES IS VISIBLE NSIDE THE BASIN FOR SEVERAL DAYS AFTER A STORM EVENT, NOTIFY THE ENGINEER FOR POSSIBLE REMEDIAL MEASURES. MOW THE BERM AT THE COMPLETION OF THE CONSTRUCTION PERIOD. REMOVE SEDIMENT WHILE THE SYSTEM IS DRY.
- NOTES:


  1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSPECTION AND THE PROPER INSPECTION AND THE PROPERTY IN THE PRO MAINTENANCE OF ALL STORMWATER AND EROSION CONTROL FACILITIES UNTIL THE PROJECT CONSTRUCTION IS COMPLETED. THE CONTRACTOR SHALL CLEAN LL COMPONENTS OF THE STORMWATER MANAGEMENT SYSTEM AT THE COMPLETION OF CONSTRUCTION, IMMEDIATELY PRIOR TO TURNING OVER OPERATION AND MAINTENANCE RESPONSIBILITY TO THE PROJECT PROPONENT
- 2. UPON COMPLETION OF CONSTRUCTION, THE OPERATION AND MAINTENANCE OF ALL COMPONENTS OF THE STORMWATER MANAGEMENT SYSTEM WILL BE THE RESPONSIBILITY OF THE SYSTEM OWNER:


VS UNION SOLAR SMART, LLC 24941 DANA POINT HARBOR DANA POINT, CA 92629

- 3. DISPOSAL OF ACCUMULATED SEDIMENT AND HYDROCARBONS TO BE IN ACCORDANCE WITH APPLICABLE LOCAL, STATE AND FEDERAL GUIDELINES AND
- 4. THERE SHALL BE NO ILLICIT DISCHARGE OF ANY WASTE OR WASTE WATER INTO THE STORMWATER MANAGEMENT SYSTEM. THE MAINTENANCE OF THE FACILITY SHALL BE UNDERTAKEN IN SUCH A MANNER AS TO PREVENT ANY DISCHARGE OF WASTE OR WASTE WATER INTO STORMWATER MANAGEMENT SYSTEM. ANY WASTE OIL OR OTHER WASTE PRODUCTS GENERATED DURING MAINTENANCE SHALL BE PROPERLY DISPOSED OF OFF SITE.




(NOT TO SCALE)






NOT TO SCALE


DIMENSIONS (IN.)







ANCHORING DETAIL




APPLICANT: VS UNION SOLAR SMART, LLC 24941 DANA POINT HARBOR DANA POINT, CA 92629


DETAILS UPPER UNION SOLAR PROJECT JUNE 19, 2023 FRANKLIN, MA


8 JOB NUMBER 3328.00

FILE: 3328 SITE PLANS


Sheet











P.O. Box 1051, Sandwich, MA 02563














DATE | REVISION

ΒY









APPLICANT:

VS UNION SOLAR SMART, LLC

24941 DANA POINT HARBOR

DANA POINT, CA 92629

DETAILS
FOR

UPPER UNION SOLAR PROJECT
JUNE 19, 2023
FRANKLIN, MA

Sheet of 9 9

JOB NUMBER

3328.00

FILE: 3328 SITE PLANS